

# **ALLAHABAD BANK**

ZONAL OFFICE, AMRITSAR  
SCO 90, DISTT SHOPPING CENTRE  
RANJIT AVENUE, AMRITSAR-143001  
Phones: 0183-2830628 Fax: 0183-2500108  
e-mail: [zo.amaritsar@allahabadbank.in](mailto:zo.amaritsar@allahabadbank.in)

TENDER FOR FURNISHING AND ELECTRICAL WORK FOR ATM SITUATED AT PHAGWARA (PUNJAB).

Quotations are invited from empanelled contractors for furnishing and electrical work for our captioned ATM premises, as per schedule of quantities (attached). Details are available at Zonal Office, Amritsar from 10.00 AM to 05.00 PM on working days.

Sealed envelopes containing bids and super scribed "Tender for furnishing and electrical work for ATM premises" situated at PHAGWARA should reach Zonal Office, Amritsar at the above address on or before 14.03.2019 by 05.00 PM. Bids will be opened on next working day at 04.00 PM.

Bank reserves the right to reject any or all the bids without assigning any reason whatsoever.

Assistant General Manager

**FURNISHING AND ELECTRICAL ESTIMATE OF ATM SITUATED AT PHAGWARA, DISTT.  
KAPURTHALA  
BELONGING TO :- ALLAHABAD BANK**

<b>Sr. no.</b>	<b>Particulars</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
1.	<p><b>Wooden Partitions:-</b>  <b>A) Full height Partitions</b>  P/F of wooden partitions consisting of 1 mm th Laminate make Century/Duro on both sides over 6mm thick Ply make Century/Duro fixed over 2"x2" th. Kail wood frames at 16" c/c both ways. The partition have 12 mm thick Glass in panels , as per design &amp; fitted with C.P. Teak wood ¾ "beading , grooves to be 4 mm wide , 4"high skirting of 1 mm th. Laminate shall be provided 1.5" th. Flush door laminated face on both sides &amp; 1 ½" x ½" C.P. Teak wood lapping , including ISI mark hydraulic door closer mortise lock of approved make, hinges, tower bolts door stoppers , handles etc. shall be provided. The door chowkats shall be made out of 4"x2" C.P. teak wood with ½" rebate all over for door panel &amp; ¾ " beading as desired. Door shall be measured in the partition area &amp; all teak wood work shall be wax/spirit polished over a coat of linseed oil &amp; finished to choice shade &amp; colour Including Pest control Treatment. ( As per IS codes) .Complete Job to the satisfaction of Architect /Employer</p>	45	Sft.		
2.	<p><b>P/F Wooden Panelling</b> made 2" x 1'-1/2" hard wooden frame with 12 mm thick wooden ply of make Century/Duro to be laminated with 1 mm thick mica of make Century/Duro and walnut shade on walls / Pillars.</p>	250	Sft.		
3.	<p>Providing &amp; Fixing False ceiling at 9'-0" ht. (as per drg.) of <b>India Gypsum Ltd.</b> (GMFSC-4.1) using 12.5mm thick Gypboard, paper tape, jointing compound, G.I. Sections marked "Gypsteel" to be placed at 4'-0" C/C in one direction and at 1'-6" C/C in other direction. The false ceiling shall be finished properly after cutting / making holes for fixing light fixtures including three coats of oil bound distemper paint etc. complete as per</p>	110/-	Sft.		
4.	<p><b>12MM THICK TOUGHENED GLASS DOORS WITH ETCHING:</b> Providing and fixing in position 12mm clear float toughened Glass for naked glass door. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., Ozone/ebco/godrej or approved equivalent make floor spring with its accessories, top pivot, center lock, 450mm glass door handles etc., along with</p>	21	Sft.		

	etching with sand blasting as per design and drawing. The maximum size of each glass shall be as per the drawing or the direction of the Engineer-in-charge. The rate is for a finished item of work et. Complete as directed.				
5.	<b>P/F Flooring vitrified tiles First</b> Grade flooring & skirting of approx. Size 600x 600mm size of approved Make and shade as per banks spec and design .The job includes Dismantling old flooring & leveling of the existing floor and fixing the tiles with recommended adhesive or cement mortar in ATM.	130	Sft.		
6.	<b>Down Lighter :-</b> Supplying, Fixing, testing & commissioning of 16 watts LED down lighter having full spread with 1100 Lumen's complete with driver. Make Philips,(Cat no. Dn 192 b LED 9s Wipro, Crompton Greaves with all requirements as per approved design & complete with connections incl extension of PVC 1.5 mm copper wire of FRLS quality in pvc flexible pie etc'	2	Nos.		
7.	<b>Ceiling Lights: -</b> Supplying & fixing, testing & commissioning of square modular fittings 36 Watts having dimension 580mmx580mm Led flat panel light Complete with Philips led & Philips driver make Hybec (LCP – 430), Phillips, Osram complete job to the satisfaction of the Architect.	1	Nos.		
8.	Supply and fix G.I. plate earth station with 600x600x6 mm thick G.I. plate including all accessories such as watering pipe and funnel and providing masonry enclosure at top with cover plate i/c excavation of pit, supplying and filling of salt charcoal, refilling of pit etc complete as reqd as per IS-3043-1987.	4	Set		
9.	Providing/ Fixing Customer Writing Ledge as per design.	1	1		
10.	<b>WIRING: -</b> Supplying, receiving, storing, handling, Fixing, laying, testing for computer terminal points. Each terminal points are connected by PVC insulated 1100 V grade 2X2.5 sqm mm wiring of first class FRLS quality cable along with 1.5 sq mm copper wire PVC insulated as earth including circuit starting from distribution board to the each terminal point. Wiring would be drawn in PVC conduits of 25mm dia with 2 mm wall thickness in concealed system laid in floor / wall chase including filling of chase with mortar etc. as required. Each terminal point would comprise 3 Nos 5A 5 Pin socket outlet controlled by one 5A switch and an indicator mounted in M.S box painted. Covered with ISI marked with chrome-plated screws. Switch Sockets should be modular type of MDS/ M.K/ North West.	1	No.		
11.	<b>3 PIN 30 A SP METAL CLAD SOCKET :- (A.C. Point)</b>	1			

	supplying, receiving, storing, handling, Fixing, laying, testing 3 PIN 30 A SP METAL CLAD industrial type socket outlet either plug top cap & chain controlled by 30A SP MCB all housed in attractive flush or surface sheet stove enameled enclosures as required & as per specifications incl 2 no. 6 mm sq copper cable conductor of FRLS quality with earthing of 1 no. 2.5 mm sq. of first class quality of FRLS quality in PVC conduits etc.				
12.	Supplying and laying of 25mm dia. heavy rigid PVC conduit (ISI marked) complete with junction box, elbows, bends, couplers and other accessories as required by chase cutting on wall through partition or over false ceiling. The work includes making good all damages to original finish, painting etc. as required.	25	Rmt.		
13.	Providing & Fixing of plug point 5 AMP with 1.5 sq.mm copper wire & .75 sq.mm earth wire including cost of switch plate, G.I box for each flats as required.(M/s Havells/Anchor roma/North West)	2	Nos.		
14.	Providing copper pipe size (5/8" and 3/8")	12	Rft.		
15.	Providing G.I. pipe 3/4" dia or PVC 1/2" dia hidden in a chase ) for drainage )	20	Rft.		
16.	Supplying and laying UTP CAT-6 cable in 2mm thick 25 mm dia ISI mark PVC conduit with accessories such as bends, junction boxes including providing and fixing I/O plates and SMB complete with all networking accessories etc complete as directed by the consultant from server to HUB, HUB to Computer Data Socket including interconnection mending good etc. as required to be complete in all respect.	30	Mtr.		
17.	Supply, installation, testing and commissioning of mounted rack 15" height made of powder coated MS sheet	1	No.		
	<b>Total</b>				