



ALLAHABAD BANK

NOTICE INVITING TENDER

Subject : Interior Furnishing / Civil Work at Tindwara Branch under ZO HAMIRPUR

Sealed tenders are invited from Bank's empanelled contractors in UP for Interior Furnishing / Civil Work at Tindwara Branch, District – Hamirpur under ZO Hamirpur

Full details and tender documents are available on Bank's website www.allahabadbank.in or may be collected from Property Department, Zonal Office Hamirpur (10/379, Rameni Tarauns, Hamirpur – 210301, UP) as per following schedule:

1	Issue of Tender Document	From 29.07.2019 to 13.08.2019
2	Last date for Submission of Tender	On or before 13.08.2019 up to 16:00 hrs
3	Opening of Tender	On 13.08.2019 at 17:00 hrs
4	Time of Completion	20 Days from the date of issue of work order
5	Scope of Work	Furnishing Work & Civil Work
6	Eligibility Criteria	Empanelled Contractor for Interior Work. Empanelment letter is to be enclosed otherwise tender will be rejected.
7	Payment Terms	No advance money will be paid. However running bills during progress of the work may be paid considering the work progress. Final payment will be made on the basis of joint measurement after completion of total work. TDS will be deducted as applicable.
8	Retention Money & Period	10% of the actual cost will be retained for 180 days and will be released after satisfaction of Bank
9	Liquidity damage for delay	If the work not completed up to the satisfaction of the Bank within the stipulated period of 20 days, the supplier shall be bound to pay the Bank , a sum equivalent to 1% of the accepted sum per week subjected to maximum deduction of 10% of the accepted tender amount by the way of liquidated damage. Once the maximum is reached, Bank may consider termination of contract and shall be entitled to terminate it.

The duly filled in sealed offer completed in all respect superscribing the “(name of work)” on top and name, address & contact no. of the tenderer at the bottom left corner of the envelope should be addressed to the under noted authority and deposit in Tender drop box **Zonal Office, Hamirpur (10/379, Rameni Tarauns, Hamirpur – 210301, UP).**

The Bank reserves the right to accept or reject any or all the tender without assigning any reason whatsoever. Late/delayed tender shall not be accepted after due date and time of submission of tender

Rananjay Singh
(Assistant General Manager)



LETTER SUBMITTING TENDER

**The Assistant General Manager,
Allahabad Bank,
Zonal Office,
Hamirpur - 210301**

Dear Sir,

With reference to the tender invited by you for the work of
Furnishing Work at Tindwara Branch under ZO HAMIRPUR

I/ We hereby offer to execute the work under contract at the respective rates mentioned in the schedule of quantities.

I/ We have seen the site and understood all the terms and conditions of the contract.

I/ We agree to execute the work as per specifications and conditions of the contract.

I/We agree to keep our offer open for a period of 30 days from the date of opening of Tender.

I/ We understand that you are not bound to accept the lowest or any other tender that you received.

Thanking You,

Yours faithfully,

Place:

Date:

(Signature of Contractor along with seal)



GENERAL TERMS & CONDITIONS

1. Sealed tenders should be addressed to **The Assistant General Manager ,Allahabad Bank, Zonal Office Hamirpur, 10 / 379 , Rameni Tarauns , Hamirpur – 210301 , UP** and should reach the Bank before 1600 hrs on **13.08.2019**
2. No tenders will be received after 1600hrs on **13.08.2019** and tenders will be opened on the same day at 1700hrs unless otherwise informed.
3. The tenders should quote the rate in figures as well as in words.
4. **All erasures and alterations made while filing the tender must be attested by initials of tenderers. Overwriting of the figures is not permitted.**
5. Joint tenders will not be considered.
6. The work is to be completed within a period of **20** days from the date of issuance of work order.
7. The rate quoted in the tender shall be inclusive of all charge of scaffoldings, lifting, tools and plants, freights, labour conditions and fluctuations in rates of excise duty, octroi , etc. No other taxes except GST as applicable will be entertained by Bank.
8. **Payment Terms :**
 - (a) No advance will be paid.
 - (b) However, one running bill of minimum amount of Rs.1.00 Lakh during progress of the work may be paid considering the progress of the work.
 - (c) Payment will be released after satisfactory completion of work, submission of bills and joint measurement.
 - (d) All payment will be made to the Vendor in Indian Rupees through IOI/NEFT/RTGS.
9. No escalation in the rates will be allowed under any circumstances.
10. **Retention Money :**

Retention Money @ 10% will be deducted from the bill and to be released after six months from the date of virtual completion provided no defects is observed during this period.
11. The successful tenderer is bound to carry out the entire work within the stipulated period in the appendix. If the work not completed up to the satisfaction of the Bank within the stipulated period of 20 days from the date of issue of work order, the contractor shall be bound to pay the employer a sum equivalent to 1% of the accepted sum per week subjected to maximum deduction of 10% of the accepted tender amount by the way of liquidated damage. Once the maximum is reached, Bank may consider termination of contract and shall be entitled to terminate it.
12. Extension of time in days will be granted by the Bank if proved that Contractor is not at fault for extending the work beyond stipulated date of completion.
13. The contractor shall remove all the malba etc. wash and clean the floors at his own cost and hand over the site in proper manner on the completion of work.
14. The tender shall acquaint himself with the site conditions, making his own arrangement for storing of material at site, lift, cartage, etc.
15. The contractors will attend to all defects noticed during the defect liability period of 180 days. If the contractor fails to attend the defects, these defects will be rectified by the Bank the expenditure incurred on this account will be recovered from the firm.
16. The contractors shall be responsible for application of labour laws compensation for injury and accident to person, whether employed by him or by his sub-contractor.



17. The contractor will take necessary precautions for carrying out the work avoiding any damage to structure/decorative part of the property. The contractor will rectify the damage at his own cost.
18. The Contractor will take all the necessary precautions for the safety and security of their workmen. In case of any accident, total responsibility will be on the Contractor.
19. The contractor shall ensure that workman employed by him for execution of work are suitably covered against Workmen's Compensation Act and that all liabilities arising out of Workmen's Compensation Act, ESIS and other legislative enactment applicable to such works and workmen shall be to contractor's account.
20. The final rate quoted by the contractor will be inclusive of GST and no extra amount will be paid on this account.
21. Income tax as applicable, if any, will be deducted at source from the contractors bill and will be deposited with the ITO as per rules.
22. The Bank may delay the progress of work without, in any way, violating the contract and grant such extension of time for the commencement of the contract as it may think proper and sufficient in consequences of such delay and the contractor shall not make claim for compensation or damage in relation thereof.
23. The contractor will not execute any extra item without Bank's permission.
24. Conditional tenders shall not be accepted by the Bank.
25. The Bank has the right to alter the nature of the work and to add or omit any items of work or to have the option of the same carried out departmentally or otherwise and such alterations or variations shall be carried out without prejudice to this contract.
26. The Bank has right to terminate the contract, if the contractor abandons the work, or fails to commence and complete the work on time or fails to abide by the contract conditions.
- 27. The firm should submit their proof of GST Identification Number along with the Bid.**
28. The Bank reserves the right to accept or reject any or all the tender, accept part of any tender or entrust the entire work to any contractor or divide the work to more than one contractor(item wise) without assigning any reasons whatsoever.
29. Arbitration: In case of any dispute between Bank & contractor, the decision taken by the Arbitrator who will be appointed by the Bank shall be final and binding to Contractor / Firm.

Declaration by the tenderer :

I have read and understood all the instructions / conditions given above and I have taken into account the above instructions / conditions while quoting the rates.

(Signature of Contractor with seal of firm)



SCHEDULE OF QUANTITIES FOR CIVIL / FURNISHING WORK

Bharat and Associates.
Architects, Engineers, Interiors &
Landscape Designers,
Shop no-1,First Floor,Jeevan Plaza
Viram Khand-5 ,Gomti Nagar,Lucknow-226010
E-Mail: bharatandassociateslko@gmail.com

Sl. No.	Description of Item	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
CIVIL WORK					
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. The work includes finishing the damaged wall with necessary repairs. (Approximate Area = 80sq.ft). All work is inclusive of scaffolding, material and labour charges.	LS	1		
2	Reinforced cement concrete work in beams / lintels, above plinth level. This includes cost of shuttering, reinforcement and RCC (1:1.5:3). All work is inclusive of scaffolding, material and labour charges. The work is to be executed as per the direction of Bank's Engineer. Reinforcement must of 16mm dia.	cum	1		
3	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel, dash fasteners , stainless steel bolts etc., of required size,	kg	10		
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	02		
5	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters.	sqft	80		



6	<p>Providing, fabricating and erecting in position totally flushed suspended false ceiling with 12.0mm thick Gypsum board, fixed to a metal frame work comprising of ceiling channel of size 80mmx26mmx0.5mm @ every 457cm centre, inter channel 45mmx15mmx0.9mm @ every 1220 cm centres, peri-meter channel 20mmx26 mm all along the wall/partitions, strap hanger suspenders 25mmx0.5mm with nuts and bolts 6.4mmx12.7mm, connecting clips 2.6mm thick, dry walls screws 25m long, soffit cleats 27mmx37mmx25mmx1.6mm thick and dash fastenes / rawl plugs 12.5 mm diax35mm long with 6mm dia bolts etc. complete with recommended fillers, paper tapes and applying two coats of acrylic emulsion paint of approved shade and make over a coat of primer including making necessary cut outs for light fittings/ ACs etc. complete as per manufacture's specifications. (Quantity as per layout plan/site requirement)</p>	Sqft	650		
7	<p>Providing and fixing 600 mm x 600 mm mineral fiber tiles false ceiling of Armstrong/Gypboard/equivalent approved make of micro look system including suspension system as per manufacturer's specifications and instructions of Architect/ Engineer complete in all respects including making cutouts where necessary for electrical lighting fittings etc. complete all as directed by the Bank. (Quantity as per layout plan/site requirement)</p>	Sqft	550		
WALL PANELLING & COLUMN ENCASING					
8	<p>Supplying and erecting Wall paneling / Column encasing (up to false ceiling) as per drawing and design and conforming to the following specifications : Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Skin membrane : 6 mm thick BWP grade plywood on face.</p>	Sqft	610		
<p>Finishing : 1.0mm thick laminate sheet of same or combination shades with grooves as per instructions. Skirting: 100mm high laminate of approved make & shade all as directed. Top Border: 150mm high laminate of approved make & shade all as directed.</p> <p>Note: Quoted rates shall include all necessary materials, accessories and labour and also for making provisions for electrical/telephone/computer wiring, conduits and switch boxes, etc. where ever required. (quantity/location should be restricted only to the central pillars in Banking hall/to hide electrical pipes/AC drain pipes/any prime location)</p>					



PARTITIONS					
9	<p>CASH CABIN PARTITIONS : <i>Supplying & Erecting full height solid cash cabin partitions (upto false ceiling as per following specifications :</i></p> <p>Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Skin membrane: To be finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/ instructions. Finishing: 1.0mm thick laminate of same or combination shades with grooves in both faces as per instructions. Skirting- 100mm high laminate of approved make & shade all as directed. Top Border: 150mm high laminate of approved make & shade all as directed. It shall have decorative aluminum grill (from 1200mm to 2100mm) fixed with teak wood beading (size – 30mm x 20mm, as per profile) with melamine finish. The job shall also include for provision of laying conduits, switch boxes etc. The erection of partition shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories, all complete up to the satisfaction of the Architect. All door opening shall have rebated teak wood framework (size – 75mm x 50mm, as per profile) on vertical (2 Nos.) and horizontal (1 No.) sides, with melamine finish and rebate of 40mm x 12mm, all complete up to the satisfaction of the Architect.</p>	Sqft	285		



	Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. (Materials for wiring, conduits, switches etc. shall be separately paid for)				
10	<p><i>Supplying and erecting full height partly glazed / unglazed partitions as per following specifications:</i></p> <p>Basic frame work: Framing shall consist of Heavy duty Aluminum Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Exposed frame members in the glazed portions shall have wider spacing (approx. 1200 mm) and be finished with 1.00 mm thick laminate of same or combination shades, over 6mm BWP grade ply.</p> <p>Skin membrane: (Opaque portion up to 900mm from floor level and from 2100mm to ceiling, finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/ instructions. Finishing: 1.0mm thick laminate of same or combination shades with grooves as per instructions.</p> <p>Glazing: 12mm thick clear float glass fixed with polished teak / steam beech wood glazing beads of approved shape (finished 12 x 25mm). Skirting- 100mm high laminate of approved make & shade all as directed.</p> <p>Top Border: 150mm high laminate of approved make & shade all as directed.</p> <p>Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. (Materials for wiring, conduits & switches etc. shall be separately paid for)</p>	Sqft	200		
11	<p><i>Supply and erecting low height opaque partitions (up to maximum 1200mm height) conforming to the following specifications :</i></p> <p>Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity.</p> <p>Skin membrane: 6 mm thick BWP grade ply on each face up to 900mm height.</p> <p>Glazing: 12mm glass in remaining portion,</p> <p>Finishing: 1.0-mm thick laminate of same or combination shades with grooves as per instructions.</p>	Sqft	100		



	<p>Edge moulds: All free top/ end surfaces shall have polished teak / steam beech wood moulds of approved shape (from 18 x 50mm sections).</p> <p>Skirting- 100mm high laminate of approved make & shade all as directed.</p> <p>Quoted rates shall include all necessary materials, accessories and labour and also allow provisions for electrical / telephone/computer wiring, conduits and switch boxes, etc. (Materials for wiring, conduits and switch boxes shall be separately paid for.)</p>				
	COUNTER & WORK STATIONS				
12	<p><i>Providing and erecting in position Cash Work Station of approx. size 1370x900x750mm (4.5'x3.0'x2.5'), made of 19mm thick block board pasted with 1.00mm laminate inclusive of a 350mm wide customer top at 1155 mm level.</i> Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished white or steam beach wood moldings of half-round profile as per drawings and instructions and 100mm high laminate of approved make & shade all as directed.</p> <p>Each cash workstation shall comprise of the drawer unit, Tea tray at top, Cash drawers with approved telescopic channels for drawer-slides, automatic locks (keys in duplicate), wire managers, space for computer CPU, modesty panel and other necessary hardware and accessories including satin finish S. S. handles of approved quality. Inner face of cash counter to be provided with 16G, M.S. sheet, painted with two coats of synthetic enamel paint of approved shade & make, over a coat of approved steel primer. Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer.</p> <p>Skirting: 100mm high laminate of approved make & shade all as directed.</p>	Rft	10		



13	<p>GLASS BARRIER ON CASH CABIN / OFFICER COUNTER <i>Providing & fixing 12mm thick clear float glass on Cash Counters at front & sides, with S S clamps/patch fittings, necessary polished beadings etc complete all as directed by the Bank.</i></p> <p>Note: Front glass to be fixed in slanting position towards inside cash area with required angle as directed. Above glass to be fixed either in two pieces. Lower piece having one semi-circular/rectangle 6” dia/long opening at customer top level & other piece to be fixed at suitable height making 3” slit for conversation with customer. In this case, only glass area to be measured for payment purpose.) In case of single piece, one semi-circular/rectangle 6” dia/long opening at customer top level & one circular hole of required dia at suitable height for conversation at centre of cash counter to be provided.</p>	Sqft	60		
14	<p>ALUMINIUM JALI ON CASH CABIN TOP <i>Providing and fixing of aluminum grill with square size 75mm x 75mm – 8mm, on top of the cash cabins etc. The grill shall be tightly stretched and nailed to a wooden frame work, made out of 50mm x 40mm teak/hard wood (with anti-termite) members at 750mm c/c approx. both ways or as per site conditions. The erection of framework shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories. All teak wood surfaces shall be painted with two coats of synthetic enamel over one coat of primer. The rate shall include cost of all materials, labour, T&P, wastages, etc. required for proper completion of work, all complete to the satisfaction of the Bank.</i></p>	Sqft	75		
15	<p>OFFICER COUNTERS <i>Supplying and erecting counters (running tables) 915 mm wide and 750mm high including drawer-cum- cabinet unit for files, space for computer CPU, wire managers, modesty panel, tea tray etc. made with 19mm thick BWP grade block board on top and supporting sides / front with necessary well seasoned Malaysian Sal/ Kail/ Mirandi wood frame work, finished on top with mirror polished 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0 mm thick laminate of approved shade and quality, including providing and fixing 450mm long key board tray of approved shade, hardware and accessories at each of the counter. All exposed edges of block board are to be provided with half round teak wood mouldings, duly polished and 100mm high laminate of approved make & shade all as directed. Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer. Skirting: 100mm high laminate of approved make & shade all as directed. Rate to include charges for brass hardware fittings as well as fixtures like sliding gear for drawers of ‘Earl Behari’ or equivalent approved make.</i></p>	Rft	19/-		



DOORS :					
16	Supplying and fixing in position overall 32 mm thick solid core hot pressed phenol formaldehyde bonded flush door finished with 1.0 mm thick laminate of approved shade and quality on both sides of the door shutter & beading on edges including cost of hardware fittings e.g. Godrej night latch / mortise lock, hinges, door closure, handles etc. of approved make and quality & making provision of peep hole of suitable size with glass& beading all-round all as directed. (Cash/Store/Other doors)	Sqft	52		
17	Supplying and fixing in position 32 mm thick solid core hot pressed phenol formaldehyde bonded partly glazed flush door shutter of approved make finished up to 900 mm from floor level with 1.00 mm thick laminate of approved quality on both sides of the door shutter & beading on edges. The upper portion of the shutter is to be provided with 12 mm thick clear float glass fixed with white or steam beech wood glazing beads of approved design, complete as per drawing. Rate to include cost of hardware fittings e.g. mortise lock, hinges, handles, door closer etc. of approved make and quality. (Manager cabin door)	Sqft.	44		
18	FLAP DOOR Providing and fixing Flap Door of min. size: 3' (B) X 2'6" (H) made of block board with approved lamination on both side, of required size with hinges/tower bolts/stopper/handles etc complete.	Sqft.	12		
19	ENTRANCE DOOR (WITH ETCHING, HEIGHT – 8' & GLASS – 12mm THICK) Providing fabricating & fixing in position twin –style door at Main Entrance made of anodized/powder coated Aluminum sections of size 100mm height x 50mm thick aluminum bottom rail, 100mm x 50mm thick vertical and top rail 100mm x 50mm thick lock rail floor spring of ISI make, clip sections and 12mm thick glass(Modi/ Saint Gobain make) including fixing the frame to brick wall/RCC/wooden surfaces with necessary fasteners to have proper fixity including all incidentals etc complete. Glass to be fixed in the grooves of the aluminum sections with necessary materials/beading etc. The job also includes cost of providing & fixing heavy duty double action hydraulic floor spring (ISI mark) in the floor, fixing the door on it, including necessary fixing materials on the lintel/bottom, bolts, locks & satin finish stainless steel decorative tubular handles(approx.300mm long) on both faces complete as per drawing and instructions. All members to be 16 gauge. The vertical shutter rail to house wool packing to act as a sealant for a gap between shutter and frame fixed glazing. The rate should also include cost for decorative etching on the glass.	Sqft	160		



20	<p>LOW / FULL HEIGHT STORAGE CABINET</p> <p>Providing and erecting in position low/ full height Storage cabinet : Made of 19 mm thick BWP grade block board including intermediate shelves as per direction, lockable shutters etc. conforming to following specifications: Shutter faces shall be finished with 1mm thick laminate of same or combination shades as per instructions with polished white or steam beech wood (6mm thick) edge lippings and 100mm high teak wood skirting duly polished/ painted as directed. Inner faces of cabinet including shutters shall be painted in approved shade. Shutters will be hung by auto-closing hinges, locks, magnetic door catcher and satin finished S. S. handles etc. of approved make. (Payment will be on the area of cabinet face). Skirting: 100mm high laminate of approved make & shade all as directed. Low Height : Maximum 450mm deep x 900 mm high Full Height : Maximum 450mm deep x 2100 mm high</p>	Sqft	110		
----	--	------	-----	--	--



21	<p>BRANCH MANAGER TABLE WITH SIDE CREDENZA INCLUDE 12mm THICK GLASS:-</p> <p>Providing and placing in position tables with top, vertical sides/dividers, skirting and modesty panel made out of 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) on all exposed surfaces. It shall also have 75mm x 40mm teak wood runners below the top and for footrest below. Every table shall be provided with a side unit (size – W-500mm, H-750mm, D-500mm approx.), consisting of 150 mm deep drawer at top and a cabinet with open able/hinged shutter below. The facia of drawer and shutter of cabinet below shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. The side unit shall have CAM locks, handles, guides, sliding units, hinges, magnetic catcher's etc. of approved make. Every table shall be provided with a pedestal unit (size – W-550mm, H-720mm, D-450mm approx.) below. The table shall have 100mm deep facia, below the top, in which keyboard drawer unit shall be adjusted. It shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. The unit shall have CAM locks, handles, guides, sliding units etc. of approved make.</p> <p>The job shall include for 6mm x 6mm grooves in between sides and open able drawers and hinged shutters. All the exposed edges of water proof board and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect. Every table top shall be provided with 12 mm thick float glass (as per profile) with polished and beveled (25mm wide) edges all complete to the satisfaction of the Architect. Approx size of table : 1830 x 915 x 750 mm (6.0'x 3.0'x 2.5') or 1524 x 915 x 750 mm (5.0'x 3'x 2.5')</p>	No	1		
----	--	----	---	--	--



22	<p>TABLE INCLUDE 12mm THICK GLASS:- Providing and placing in position tables with top, vertical sides/dividers, skirting and modesty panel made out of 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) on all exposed surfaces. It shall also have 75mm x 40mm teak wood runners below the top and for footrest below.</p> <p>The facia of drawer and shutter of cabinet below shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. Every table shall be provided with a pedestal unit (size – W- 465mm, H-720mm, D-450mm approx.) below. The table shall have 100mm deep facia, below the top, in which keyboard drawer unit shall be adjusted. It shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. The unit shall have CAM locks, handles, guides, sliding units etc. of approved make.</p> <p>The job shall include for 6mm x 6mm grooves in between sides and open able drawers and hinged shutters. All the exposed edges of water proof board and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect. Every table top shall be provided with 12 mm thick float glass (as per profile) with polished and beveled (25mm wide) edges all complete to the satisfaction of the Architect. Approx Size : 1372 x 750 x 750 mm (4.6’x 2.5’x 2.5’)</p>	No	1		
23	<p>PAINTING WORK Painting on undecorated / decorated wall and ceiling surfaces with two or more coats of acrylic emulsion (Asian/Berger make) (as / shade approved by the Architect) of approved brand. It shall include for preparing the surfaces clean, even and smooth with thoroughly brushing with broom, scratching with patti and sand papering respectively, so that the surfaces are free from oil, grease, dirt, mortar droppings & other foreign and loose matter. It shall also include for preparing the surface and filling of holes with plaster of paris before priming coat of whiting / approved primer.</p> <p>The rate shall include cost of all materials such as plaster of paris, whiting /primer, glue (Fevicol), indigo / stainer, brushes, sand paper, patti, dhoti, broom stick, clean water with storage and other containers, labour, scaffolding / ladder charges, cleaning of floors and other sundries etc., all complete to the satisfaction of the Architect.</p>	Sqft	4560		
	MISCELLANEOUS ITEMS :				



24	<p>SLIP & CUSTOMER WRITING DESK</p> <p>Providing and fixing in position (with rear wall) slip and customer writing desk (as per design) of overall size – 1200mm x 450mm x 300mm. The fixing shall include for expansion bolts, cleats, clamps, bolts, nuts, screws, rivets and other anodized accessories, all complete up to the satisfaction of the Architect.</p> <p>The writing top and facia/sides shall be made out of 19mm thick water proof board with 1mm thick laminate (as per shade approved by the architect), on all sides and . It shall be laid over the base of 19mm thick water proof board (already considered in various items.) and fixed with araldite. It shall include for beveling and polishing at all the exposed edges. The rate shall include cost of all materials, labour, scaffolding, wastages, polishing and T& P etc. It shall be made out of 12mm thick water proof plywood (two surfaces of 6mm thickness, fixed together, where required) on rear and both sides. The front shall be made out of 12mm thick glass (as per profile). It shall be fixed in the grooves, made in side members, in an inclined manner (as per profile in drawing enclosed) with a gap of 75mm (max.) in between. The space shall be further divided in four equal parts with help of 12mm thick water proof plywood. All edges of the glass shall be polished. All the exposed edges of water proof board and plywood shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect</p>	No	1		
25	<p>CHEQUE DROP BOX / SUGGESTION BOX</p> <p>Supplying and erecting cheque drop box / suggestion box (over all size 400mmx150mmx600mm) made of 19 mm thick BWP grade ply board and curved portion at top made out of 90mmx90mm C.P. teak/steam beach wood section. A slit opening of 10mmx150mm is to be provided at the top of the box. An openable shutter of 259mmx262mm size made of 19 mm thick BWP grade block board is to be provided. The entire exposed timber surface including all free edges is to be finished with 1mm thick laminate sheet of combination shade. Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer. Rate to include cost of necessary hardware fittings e.g. hinges, lock, knob, etc. of approved design and quality.</p>	No	2		



26	<p>NOTICE BOARD</p> <p>Providing and fixing in position notice board (as per design) of size – 900mm x 600mm x 150mm. The sides shall be made out of 19mm thick water proof board with 1mm thick laminate (as per shade approved by the architect) on all exposed surfaces.It shall have 12mm thick tack The front shall have 6mm thick float glass sliding shutter in two parts.</p> <p>It shall also have 19mm wide two track aluminum channel for sliding arrangement, all around, along with locking arrangement. Board (Make – Cellotex or equivalent) wrapped with stretched blazer cloth (Make- Raymonds), of Rs. 200.00 per Mt. (approx.) in colour and pattern approved by the Architect. It shall be fixed with help of nail/partial wood (sect. 19mm x 25mm) frame work. It shall be covered with 6mm thick water proof plywood, on the back. All the exposed edges of water proof board and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect.</p>	No	1		
27	<p>ETCHING WORK & BANK LOGO FOR BRANCH</p> <p>Etching for Toughened glass (Branch and ATM), Etching for Cash Cabin Glass, Etching for Front counters.</p> <p>Etching work on glass with chemicals (as per design and profile) as and where required. The rates shall include cost of all materials, labour, T& P, wastage, transportation etc. required for proper completion of work. It shall be made out of following profile.- Bank’s logo (300mm dia. / 300mm x 300mm).All complete to the satisfaction of the Architect.</p> <p>Etching work on glass with chemicals (as per design and profile) as and where required. The rates shall include cost of all materials, labour, T& P, wastage, transportation etc. required for proper completion of work.</p> <p>It shall be made out of following profile.-Bank’s logo (300mm dia. / 300mm x 300mm).All complete to the satisfaction of the Architect.</p>	No	150		
28	<p>MAIN PANEL BOXING</p> <p>Providing & fixing in position 2”x2” kailwood frame and finished with 6 mm thk. Ply on Outer sides with 1.0 mm thk & Inner Side of Storage Paste 1.5 Thick Aluminum Tubular Section of Approved Colour Pattern . Front Side of Storage Aluminum Jali for Ventilation of the Panel & the Measurement of the Storage only front Facia of the Storage (Lenth x Height). All work Complete to the Satisfaction of the Bank /Architect.</p>	Sqft	40		



29	ACP PANNELING ACP Panneling & Rolling Shutter Box. Frame Work-2" X 2" X 1.5 mm thick Aluminium Tubular section (Horizontal/Vertical) Jindal Make Aluminium Composite Panel-3.0mm thick of approved colour with bonding material	Sq.ft	180		
TAXABLE AMOUNT (Rs.)					
GST AMOUNT (As applicable) (Rs.) %					
GROSS AMOUNT (Rs.)					
Amount in Words :					
<u>List of approved make</u>					
Wood : First class steam beach wood or as specified					
Polish : MRF Polyurethane					
Soft Board : Celotex					
Block Board: Century / Archidply / Greenply (BWP Grade)					
Ply Board: Century / Archidply / Greenply (BWP Grade)					
Laminates:- For Partitions/Tables/Counter Surface:- Century Ply :303- Bodensee Beech, Sunmica : E-224/1224-Steam Beech, Formica-FI-1224(SF)-Steam Beech-I, Greenlam : 685-Swiss Pear					
<u>For Border & Skirting:-</u> Century:191- Radiant Red, Sunmica : G-448/1448-Teracotta, Formica- FI-1517(SF) Sienna, Greenlam: 165- Light Red					
Glass: Modi/Saint Gobin					
Gyp Board: India Gypsum / Armstrong / St Gobain					
Aluminium Sections : Hindalco / Jindal					
Locks/Handles: Godrej / Harrison / Hettic					
Magnet Catcher : Supreme / Excel					
Drawer Sliding Fittings: Earl Bihari (EBCO)/Godrej/ Hettich or equivalent approved.					
Floor Spring/Door Closer: Hemco / Hardwin/ Godrej or equivalent approved.					
Paint : Asian Paints / Berger / Nerolac					
Other materials: ISI mark & approved by the Bank.					

(SIGNATURE OF CONTRACTOR WITH STAMP)