

**ALLAHABAD BANK (Zonal Office), AGRA. SHOP NO 12, CROSS ROAD MALL,**  
**Pt. DEEN DAYAL UPADHYAY PURAM SIKANDRA AGRA**  
e-mail: zo.agra@allahabadbank.in

**NOTICE INVITING TENDER**

**ALLAHABAD BANK, ZONAL OFFICE, AGRA, INVITES SEALED Quotations FROM THE EMPANELLED CONTRACTORS OF OUR BANK FOR INTERIOR FURNISHING and ELECTRICAL WORK OF ALLAHABAD BANK AT BURHPUR BRANCH, FARRUKHABAD UNDER ZONAL OFFICE AGRA.**

1	Description of works	Interior Furnishing and Electrical work at new Premises of Burhpur Branch at Farrukhabad under ZO Agra.
2	Earnest money deposit	Rs.20,000/- (Rs. twenty thousand only) In form of D. D. / IOI only.
3	Cost of Tender Documents	Rs.300.00/- (Rs. Three hundred only) (Non-Refundable) In form of D. D. / IOI only.
4	Last date and time of receipt of tenders	<b><u>03.06.2019 up to 3:00 PM</u></b>
5	Address where the tenders are to be submitted	The Zonal Head, Allahabad Bank, SHOP NO 12, CROSS ROAD MALL, Pt. DEEN DAYAL UPADHYAY PURAM SIKANDRA AGRA.
6	Date and time of opening of tenders	<b><u>03.06.2019 at 3:30 PM</u></b> In case the date of opening of tenders is declared as a holiday, the tenders will be opened on the next Working day at the same time.
7	Place of opening of tenders	Allahabad Bank, SHOP NO 12, CROSS ROAD MALL, Pt. DEEN DAYAL UPADHYAY PURAM SIKANDRA AGRA.
8	Defects liability period	12 Months from the date of completion
9	Validity of offer	90 Days, which may be extended further by mutual agreement.
10	Liquidated Damages/ Penalty	1% of the contract value per week subject to a maximum of 10% of the contract value
11	Retention money	<b>10% of total bill amount</b> (Including initial security Deposit to be deducted from running bills if any).
12	Release of Retention money	After 14 days of the end of defects liability period i.e. 12 months, provided the work has been satisfactory in the past 12 months i.e. defect liability period and no Defect has been there in the work.
13	Date of Commencement of Work	Latest by 7 (Seven) days from the date of receiving Work order.
14	Time allowed for completion	THIRTY days from the date of commencement of The work.
15	Refund of total security	The initial security deposit comprising of EMD shall be refunded to the contractor upon issue of certificate of virtual Completion by the Architect, provided satisfaction to the Bank.

16	Minimum value of work for interim certificates	N.A.
17	Minimum period of submitting interim bills	N.A.
18	Contractor All Risk (CAR) Policy certificate to be submitted	30 (Thirty) days from the date of work order issued or 7 (Seven) days from the date of work order received Whichever is later?

\* For any query please contact empanelled Architect on telephone Nos. 9319102421 (Mr. Archana Yadav).

**Mode of Submission of Tender:** The tender shall be submitted in **two cover system** in accordance with the procedure detailed herein below. Specified documents shall be sealed in envelopes of appropriate size each of which shall be sealed.

- 1) First Envelope marked **cover 1** shall contain Earnest Money Deposit, covering letter, clarification (if any), **technical bid** and commercial terms.
- 2) Second Envelope marked **cover 2** shall contain only the priced Bill of Quantities, i.e. **Financial Bid** along with an additional photocopy of priced Bill of Quantities.
- 3) Envelope marked **cover 3** shall be of adequate size and shall contain envelopes marked **covers 1 & 2** and shall be properly sealed. This envelope shall be endorsed on the outside face as under:  
**"TENDER FOR FURNISHING AND ELECTRICAL WORKS AT NEW PREMISES OF BURHPUR BRANCH, FARRUKHABAD, ALLAHABAD BANK UNDER ZONAL OFFICE AGRA"**.

**Opening of Tender:**

- 1) The envelope marked **cover 3** containing the tender documents as per instructions at (a) above shall be opened in the Allahabad Bank, Zonal Office at **03:30 p.m.** on **03.06.2019** in the presence of authorized representatives of those tenderers who chose to remain present.
  - 2) Envelope No. 1 containing the Earnest Money Deposit, covering letter, Technical bid, terms and conditions will be opened first and if the Earnest Money Deposit is not found as prescribed and/or the technical bid is/are unsigned, the tender shall be rejected and other sealed envelope will not be opened accordingly.
  - 3) After opening of **cover 1** and after evaluating the clarifications / conditions, if any, stipulated by the contractors, **cover 2** containing priced B.O.Q. i.e. Financial Bid, will be opened.
- **Incomplete tenders shall be rejected and no further communication in this regard shall be entertained.**
  - **Allahabad Bank has the right to accept / reject any or all tenders without assigning any reasons whatsoever.**

**Date: 17.05.2019**

**The Zonal Head**

**NOTICE TO CONTRACTORS**

**EMPANELLED CONTRACTORS OF ALLAHABAD BANK FOR INTERIOR  
FURNISHING WORKS AT EXSITNGING PREMISES OF BURHPUR BRANCH,  
FARRUKHABAD, UNDER ZONAL OFFICE AGRA**

**To**

.....  
.....  
.....

Dear Sir,

1. Allahabad Bank takes the pleasure in inviting you to tender for the above said work. Sealed tenders should be addressed to "The Zonal Head, Allahabad Bank, Zonal Office, agra and super-scribed for the proposed "Interior furnishing and Electrical works at New premises of burhpur Branch, Farrukhabad, under Zonal Office Agra" and **deposited at the Office of ALLAHABAD BANK (Zonal Office), AGRA. SHOP NO 12, CROSS ROAD MALL, Pt. DEEN DAYAL UPADHYAY PURAM SIKANDRA AGRA.**
2. The tenderer shall not make any correction/alteration on these documents.
3. The Agency is advised to inspect and examine the sites and satisfy himself as to the condition prevailing at sites and its surrounding extent of work, scope and conditions under which the work is to be executed. The contractor shall also satisfy himself about the accessibility to the premises.
4. The rate quoted in the tenders shall be inclusive of all materials as required.
5. Work will be completed within the period of **30 days** from the date of issue of tender or work order whichever is earlier. If the work be not completed to the satisfaction of employer within the stipulated period, the contractor will be bound to pay to the Employer a sum equivalent to 1% of the accepted tendered value per week subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains uncommenced or unfinished after expiry of the completion date.
6. Contractors are required to submit time schedule of work. After completion of work, cleaning of floors, walls etc are to be done to the satisfaction of engineer-in-charge.
7. After completion of jobs, the site shall be cleared of all rubbish in all respect. All holes shall be filled up and finished as per existing finishes.
8. If an extension of time of completion of the work is sought on the grounds of having unavoidable hindrances in its execution or any other ground, the contractor shall apply in writing to the officer – in - charge of the Estate Management department with full details of the circumstances which is causing such an extension. All the decisions in this regard taken by the Bank shall be binding to the contractor.
9. The tenderer must obtain for himself on his own responsibility and at his own expenses all the information's which may be necessary for the purpose of filling this tender and for entering into a contract for the execution of the same and must examine the drawings and inspect the site of the work and acquaint himself with local conditions and matters pertaining thereto, nature and requirements of the works facilities of transport condition, access and storage of material. The tenderer shall provide in their tender for cost of carriage, freight and other charges as also for any special difficulties and including police restriction for transport etc. for proper execution of the works as indicated in the drawings. The successful tenderer will not be entitled to any claim of compensation for difficulties faced or losses incurred on account of any site condition which existed before the commencement of the work or which in the opinion of the architects might have deemed to have reasonably been inferred to be so existing before commencement of work.

10. Each of the tender documents is required to be signed by the person or persons submitting the tender in token of his having acquainted himself with all the conditions/ specifications as may be laid down. Any tender with any such document / paper not signed or with details marked as applied for shall be out rightly rejected. It will be obligatory on the part of tenderers to sign on all the pages of the tender. Conditional tenders shall be rejected. If any of the documents are missing or unsigned the tender shall be considered as invalid also rates not filled up in any item or marked as actual plus percentages shall make the tender as invalid and shall be rejected.
11. The tender form must be written/typed in ink, not by the pencil, otherwise the tender will be considered invalid by the Owners in its discretion and the tender will be rightly rejected.
12. Any additions and alterations made while filling the tender must be attested by initials of the tenderer. Over writing of figures is not permitted. Failure to comply with either of these conditions will render the tender void. No advice or any change in rates or conditions after submission of the tender will be entertained.
13. The tenderer shall deposit with Bank **Rs.20,000.00 (Rs. twenty thousand only)** by demand draft/ IOI only as earnest money which amount shall be forfeited in the event of refusal or delay in signing the contract within seven days from the date of issue of acceptance letter for tender. The earnest money of the successful tenderer shall be adjusted towards security deposit. A tender not accompanied with the requisite earnest money in demand draft shall stand rejected. EMD of all unsuccessful parties shall be refunded. The deposits of the unsuccessful tenderers will be returned without any interest, after a decision is taken regarding the award of the contract.
14. Security deposit equivalent to 10% from each running bill shall be deducted and shall be returned after expiry of defect liability period of 12 months from the date of virtual completion as certified by the architect, provided satisfaction to the Bank. Earnest Money Deposit would be adjusted with the security deposit in the final bill.
15. Within three working days of the receipt of intimation from Allahabad Bank of the acceptance of his/their tender, the successful tenderer shall be bound to implement the contract by signing an agreement onRs.500/- non- judicial stamp, in accordance with the terms and conditions of the contract, but the work order or the written acceptance by Allahabad Bank of a tender will constitute a binding agreement between Allahabad Bank and the contractors so tendering whether such a formal contract is or not subsequently entered into.
16. All compensation or other sums of money payable by the contractor to Allahabad Bank under the terms of this contract may be deducted from the security deposit or from any other sum that may be or may become due to the contractor on any account whatsoever and in the event of the security deposit being reduced by reason of such deductions the contractor shall within 7 days of being asked to do so make good in cash or cheque any sum or sums which may have been deducted from his security deposit.
17. In case where the same item of work is mentioned at more than one place in the schedule of quantities the lowest of the rates quoted by the contractor shall be taken into account for payment of the item.
18. The rates quoted shall be firm and shall include all costs, charges, freight, allowances, taxes, levies, taxes, royalties etc. as applicable. GST should be mentioned separately. Taxes like TDS etc. shall be deducted from the bill(s) of the contractor as per prevailing rates. In case of any exemption claimed in this regard the contractor shall submit requisite certificates from the respective departments to Allahabad Bank in advance.
19. The work should be completed within **THIRTY (30) DAYS** from the date of the work order issued to the contractor to commence the work. If the contractor fails to complete the work by the scheduled date of completion or within any sanctioned extended time limit he will have to pay damages as stipulated for the period that the work remains incomplete. The samples of all the materials and work items shall be got approved from the consulting architect before proceeding further. The drawings contain sketches

showing salient features, details at the various scale indicating extent of work and specifications to be followed. These can be modified by Allahabad Bank from time to time in accordance with technical requirements at the site.

20. Any damage done to the property of Allahabad Bank during execution of work shall be the responsibility of the contractor and it shall be made good by him at his cost to the entire satisfaction of consulting architect/ Allahabad Bank. The architect & engineer shall have full powers to get the material or workmanship etc. inspected and tested by an independent agency for its soundness and adequacy at the cost of contractor. Prior approval of brand and material of ISI make as per the general material specifications is sole discretion of engineer in-charge binding upon the contractor.
21. The quantities contained in the schedule are approximate only. The work as actually carried out and done will be measured up from time to time for which payment shall be made subject to the terms and conditions of the contract.
22. No mobilization advance shall be released to the contractors at the start of work. Only one running payment shall be made to the contractor as per the work progress after verification of running bill by the architect/ Bank. Tender shall be valid for a period of 3 months from the due date of its submission. However, Allahabad Bank is not bound to accept the lowest or any tender and reserves the right to accept or reject any or all tenders either in whole or in part, without assigning any reason for the same. Conditional tenders are not acceptable and shall be summarily rejected. Further, no communication in this regard will be entertained.
23. All items of work mentioned in the schedule of quantities are to be deemed and paid as completed works in all respects and details including preparatory and finishing works involved directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charge will be allowed in this connection. In the case of lump sum charges in the tender in respect of any item of works, the payment of such items of work will be made for actual work done on the basis of lump sum charges as will be assessed to be payable by Allahabad Bank/ Architect.
24. The tenderer should note that the tender is strictly on item rate basis and their attention is drawn on the fact that the rates for each and every item should be correct, workable and self-supporting and based on the specification schedule submitted herewith. Financial bids marked as percentages above or below the PWD BSR / CPWD BSR or any such other instrument would be summarily rejected. If called upon by Bank/ Architects detailed analysis of any or all the rates will have to be submitted. The Architects/ Bank is not bound to recognize the contractor's analysis.
25. All designated material samples will be tested and inspected at contractors expense if desired by the Bank at designated laboratories.
26. The contractor shall conform to the provision of all local byelaws and acts relating to the work and to the regulations etc. of the government and local authorities and of any company with whose system the building is supposed to be constructed. The contractor shall give all the notices required by the said act, rules and regulation and byelaws etc. and pay all charges/ fees payable to such authorities for execution of the work involved. The cost if any shall be deemed to have been included in his quoted rates, taking into account all liabilities for licenses, fees for footpath encroachment, restoration etc. and shall indemnify the employer against such liabilities and shall defend all actions arising from such claims of liabilities.
27. Certificates of purchase of company specified items/ units like chairs, tube lights, electrical fixtures and fittings and any such other units as deemed necessary by the architect/ bank's engineer have to be attached by the contractors from the authorized distributors/ dealers/ company showroom along with the furnishing bills.
28. For any further drawings/ details/ clarifications please have an advice through the Bank.
29. Bank reserves the right to cancel all or any of the tenders and can change / drop/ reduce the quantities/ items mentioned in the schedule at any time, before placing of

- the order or even during execution. The decision of the Zonal Manager in all matters pertaining to the work execution shall be final and binding.
30. Prior approval to be obtained in writing from project architect/ bank if any change made in the design/ execution of works.
  31. Final bill will not be processed until rectification of defects pointed out by the project architect/ bank is carried out by the contractor.
  32. Rates must be quoted for complete work at site inclusive of all costs, freight, taxes and charges, etc. GST must be quoted separately. All taxes and duties including sales Tax, E.S.I. charges etc. as applicable, Central or Octroi, Royalties, Interstate transportation etc. on works and materials required for use in this project shall be entirely borne & payable by the contractor. The Employer will not entertain any claim whatsoever in this respect. The rates shall be firm and shall not be subject to cost escalation of labour and material and exchange variations, labour conditions and other conditions whatsoever.
  33. Tax deductions like Income tax, will be made as per the prevailing rates and norms from the contractor's account bills and necessary certificates/ challans may be claimed by the contractor from the bank after completion of formalities.
  34. Certified photocopies of – GSTIN, PAN Card, VAT Registration and VAT (exemption if any) shall need to be submitted along with all bills for issue of payment.
  35. This tender should be accepted, I / We here by agree to abide by and full the terms and provisions of the said conditions of contract annexure here to.
  36. Retention money @10% of the gross value of each interim bill. The retention money will be refunded 14 days after the end of defect liability period i.e. 12 months from the completion certificate by the Architect, subject to satisfaction to the Bank and provided he/she/they has/have satisfactorily carried out all the works and attended to all defects in accordance with the conditions of the contract, including the site clearance.
  37. After opening the envelope containing the offer on the standardized conditions and opening of the priced tender, no correspondence will be entertained.
  38. **Incomplete tenders shall be rejected and no further communication in this regard will be entertained.**
  39. **Allahabad Bank has the right to accept / reject any or all tenders without assigning any reasons whatsoever.**
  40. The tenders shall remain open for acceptance by the bank for a period of 90 days from the date of opening of the second cover containing the priced tender, which may be extended further by mutual agreement and the tender shall not be withdrawn by the tenderer during validity period failing which EMD will be forfeited.
  41. The tendered must use only the Tender forms / documents issued by the bank. If given space falls short for furnishing the information's, separate sheets may be added duly signed by the contractors.
  42. The L-1 tendered must sign an agreement with Bank on non judicial stamp paper of Rs.500/- should be signed compulsorily before commencement of work.
  43. The L-1 tendered must sign an Indemnity Bond on non judicial stamp paper of Rs.500/- should be signed compulsorily before commencement of work.
  44. Electrical panel arrangement should be as per the relevant BIS standards.
  45. Earthing work should be as per relevant IS code.
  46. Each page of the tender document must be signed by the contractor.
  47. All erasures and alterations made while filling the Tender must be attested by initials of the Tenderer. Overwriting of figures is not permitted. No advice of any change in the rate or conditions after the opening of the Tender will be entertained.
  48. The Tender submitted on behalf of a Firm shall be signed by all the Partners of the Firm or by a Partner who has the necessary authority on behalf of the Firm to enter into the proposed contract. Otherwise the Tender may be rejected by the Owners.
  49. The Contractor shall not assign the contract. He shall not sublet any portion of the Contract except with the written consent of the bank. In case of breach of these conditions, the bank may cause the Architect to serve a notice in writing on the

- Contractor rescinding the Contract where upon the Security Deposit shall stand forfeited to the bank, without prejudice to his other remedies against the Contractor.
50. The Contractor shall carry out all the work strictly in accordance with Drawings, details and instructions of the Architect/Bank. If changes have to be made in the design. The same will be done with the prior approval in writing of the bank/ Architect. Contractor shall carry out the same without any extra charge. The Bank's decision in such cases shall be final and shall not be open to arbitration.
  51. A Schedule of Probable Quantities in respect of each work and specifications accompany these special conditions. The schedule of Probable Quantities is liable to alteration by omissions, deductions of additions at the discretion of the Architect. Each Tender should contain not only the rates but also the value of each item of work entered in a separate column and all the items should be totaled in order to show the aggregate value of the entire Tender.
  52. The Tenderer must obtain for himself on his own and at his own expenses all the information which may be necessary for the purpose of making a Tender and for entering into a Contract and must inspect the site of the work and acquaint himself with all local conditions, means of access to the work, nature of the work and all matters appertaining there to.
  53. The successful Tenderer is bound to carry out any items of work necessary for the completion of the job even though such items are not included in the quantities and rates. Schedule of instructions in respect of such additional items and their quantities will be issued in writing by the Architect with the prior consent in writing of the Bank.
  54. The successful tenderer should make his own arrangements to store all the materials required for the work. No advance against materials purchased and brought at site will be made. The contractor will have to keep the materials at site under their safe custody and at their risk and cost. The Bank/ Owners of premises are not responsible for damages and losses of such materials brought at site.
  55. Contractors are requested to note that no extra item of deviated item of work to be executed without taking prior permission from Bank/Architects, if the extra item of deviated item of work is executed without taking prior permission, Bank shall not be held responsible for the payment of such works executed.
  56. Work should be executed only at the site under the supervision of a competent supervisor with strict quality control & workmanship Bank/ Architects may inspect the work during its execution at site.
  57. No deviation in the specification and make would be acceptable.
  58. The work shall be executed in coordination with the other furnishing agencies such as A. C., Interior furnishers, Civil and other such contractors.
  59. All the electrical items shall be strictly according to the bank's specifications and ISI marked.
  60. All furniture such as counters, tables, etc. shall be computer compatible and shall have key board tray, CPU stand, etc.
  61. The names of partners of the contractor's firm to be mentioned below :
    - (i)
    - (ii)
    - (iii)Name of the partner of the firm authorized to sign  
Or  
Name of person having Power of Attorney to sign the Contract.  
(Certified true copy of the Power of attorney should be attached)
  62. The contractors are advised to inspect the drawings available with the Bank before submitting the Tender.

63. There must be submission of “Single Line Diagram” for electric works and “As built” drawings in original (3 sets) should be a mandatory criteria before releasing final payments to contractor.

I / We hereby declare that I / We have read and understood the above instructions for the guidance of Tenderers.

Place:  
Date:

Signature, Seal and address of Tenderer



**PROFORMA**  
(On Non Judicial Stamp Paper of Rs.500/-)  
**FORM OF INDEMNITY BOND**

KNOW all men by these presents that I/We \_\_\_\_\_ do hereby execute indemnity Bond in favor of \_\_\_\_\_ having their Registered Office at \_\_\_\_\_ and amongst other offices at No. \_\_\_\_\_ and M/s. \_\_\_\_\_ having their office at \_\_\_\_\_ on this \_\_\_\_\_ day of \_\_\_\_\_ 20.

WHEREAS the \_\_\_\_\_ have appointed \_\_\_\_\_ as the Furnishing contractors for their proposed building at \_\_\_\_\_ and M/S \_\_\_\_\_ as their Architects/ Engineers.

**THIS DEED WITNESS AS FOLLOW:**

I/We \_\_\_\_\_ hereby do indemnify and same harmless (1) \_\_\_\_\_ and

(2) M/s \_\_\_\_\_ against and from:

- 1) Any third party claims, civil or criminal complaints/ liabilities , site mishaps and other accidents or disputes and / or damages occurring, or arising out of any mishaps at the site due to faulty work , negligence , faulty construction and / or for violating any law, rules and regulations in force, for the time being while executing/ executed civil works by me / us;
- 2) Any damages, loss or expenses due to resulting from any negligence or breach of duty on the part of me/us or any sub-contractor/s if any, servants or agents.
- 3) any claim by an employee of mine/ours or of sub - contractors if any, under the workmen compensation act and Employers Liability Act, or any other law, rules and regulations in force for the time being and any acts replacing and .or amend the same or any of the same as may be in force at the time and under any law in respect of injuries to persons or property arising out of and in the course of the execution of the contract work and/or arising out of & in the course of employment of any workmen / employee.
- 4) any act or omission of mine /ours or Sub-contractor/s if any , our / their servants or agents which may involve any loss, damage , liability , civil or criminal action.

IN WITNESS WHEREOF THE \_\_\_\_\_ has set his / their hands on this day of \_\_\_\_\_ 20\_\_.

SIGNED AND DELIVERED BY THE

AFORESAID \_\_\_\_\_

IN THE PRESENCE OF  
WITNESS 1)

2)

**ARTICLES OF AGREEMENT**

10. This agreement is made on \_\_\_\_ day of \_\_\_\_\_ 20... between **ALLAHABAD BANK(Zonal Office),AGRA. SHOP NO 12, CROSS ROAD MALL, Pt. DEEN DAYAL UPADHYAY PURAM SIKANDRA AGRA.**

(hereinafter called "**The Bank**") on one part and .....  
(hereinafter called "**The Contractor**") on the other part.

WHEREAS the Employer is desirous of certain works to be executed viz. "**Interior Furnishing and Electrical works at new premises of Burhpur Branch, Farrukhabad, under Zonal Office Agra**" and has tender by contractor for the execution, completion and maintenance of such works. Now this agreement witnesses as follows:

1.1 In this agreement words and expression shall have the same meaning as are respectively assigned to them in the said conditions of contract hereinafter referred to.

1.2 The following documents shall be deemed to form and to be read/ construed as part of this agreement, viz.,

- i) Original tender documents
- ii) Relevant correspondence i.e. all letters/correspondence forming part of contract and referred to in acceptance letter.
- iii) Acceptance letter
- iv) Bill of quantities
- v) The drawings
- vi) Time and progress chart
- vii) Other Additional documents as required
  - A)
  - B)
  - C)
- viii) Articles of Agreement

1.3 The aforesaid documents shall be taken as completely and mutually explanatory of one another, but in the case of ambiguities or discrepancies the latest documents issued by the Bank shall prevail over all earlier documents.

Give the name, designation and address of the Contractor.

1.4 In consideration of the payment to be made by the Bank to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Bank to perform, execute complete and maintain the work in conformity in all respects with the provision of the contract.

1.5 The Bank hereby covenants to pay the Contractor in consideration of the execution, completion and maintenance of the works such as shall become payable hereunder at the time (s) and in the manner prescribed in the said conditions and price schedule of quantities / bill of quantities prescribed in the contract.

IN WITNESSES where of the parties hereto have caused their respective common seals to be hereunto affixed (or have hereunto set their respective hands and seals) the day, month and year first above written.

**SIGNED AND SEALED AND DELIVERED BY THE**

Said \_\_\_\_\_  
(Name \_\_\_\_\_  
on behalf of the contractor  
in the presence of  
Name \_\_\_\_\_

Said \_\_\_\_\_  
(Name \_\_\_\_\_  
on behalf of the employer  
in the presence of  
Name \_\_\_\_\_

\*\* This form is included in the tender documents only for the information of the tenderers. Only the successful tenderer will be in due course required to complete the form.

**ALLAHABAD BANK : ZONAL OFFICE****CROSS ROAD MALL SINKANDARA BODLA ROAD, AGRA.****TENDER FOR THE INTERIOR FURNISHING WORK (BRANCH+ATM)  
BADPUR, FARRUKHABAD.**

S.N.	ITEM DESCRIPTION	QTY	UNIT	Rate	AMONT Rs.
1	<i>Wall Panelling/column encasing (upto false ceiling height) works as per Basic frame work Well seasoned hard wood sections, treated with two coats of wood preservatives minimum 50x25 mm,at suitable horizontal/vertical spacing not exceeding 600 mm c/c. Skin Membrane 6 mm thick BWR grade plywood with grooves formed as desired as per Finishing 1 mm thick laminate sheet of same or combination shades as per instructions Skirting 100 mm high x 12 mm thick polished 2nd class teak wood skirting with NC lacquer finish.Quoted rates shall include all necessary materials,accessories and labour and also allow provisions for electrical/ elephone/ computer wiring conduits and switch boxes,etc complete with necessary jacking/thickening of panels to accomodate conduits/switch boxess.(materials for wiring conduits and switch boxes shall be seperately paid for.</i>	506.00	sqft		
2	<i>Supplying and erecting full height partitions(up to false ceiling height) as per drawing and conforming to the following specifications:Basic Framework Well seasoned hard wood sections,treated with two coats of wood preservatives, 60 mm x 40 mm (minimum) 600 mm horizontal or vertical spacing as per site conditions.Vertical members shall be suitably, anchored and at ceiling level to ensuure rigidity. Exposed frame members in the glazed portions shall have wider spacing (approx. 1800 mm clear) as per instructions.Exposed members shall be finished with 1.00 mm thick laminate sheet of same or combination shades,over 6 mm grooves BWR grade plywood facing including 4x6 mm grooves at locations as per instructions. inishing</i>				
	<i>1.0 mm thick laminate sheet of same or combination shades as per instructions . Skirting 100 mm high x 12 mm thick polished teak wood on both faces , with NC lacquer in mat finish.Glazing 6 mm thick clear float glass fixed with continous steam beech/teak wood glazing beads of approved shape(finished 35 x 25 mm) all round,polished and coated with NC lacquer finish. The rate should also include cost for decorative etching on one side of the glass. Quoted rates shall include necessary material,accessories and labour and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes , etc(Materials for wiring conduits and switch boxes shall be seperately paid for. ) (with complete hudraulic closer , mortice lock, door stoper &amp; Godrej Night Latch (ISI mark)</i>	560.00	sqft		
3	<i>Supplying and erecting low height partitions ( up to max.1200 mm.High) as per drawing and conforming to the following specifications: Basic Framework Well seasoned hard wood sections,treated with two coats of wood preservatives, 60 mm wide x 40 mm (minimum) at maximum 600 mm horizontal or vertical spacing as per site conditions. Skin Membrane 6 mm thick BWR grade plywood on each face, with grooves formed as per drawing/instruction. Finishing 1mm thick laminate sheet of same or combination shades as per instructions.Edge moulds All free top/end surfaces have polished teak wood skirting with NC lacquer finish.Skirting .</i>				

	<i>100 mm high x 12 mm thick polished teak wood skirting with NC lacquer finish. Quoted rates shall include all necessary materials, accessories and labour and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes, etc. (Materials for wiring conduits and switch boxes shall be separately paid for.)</i>	50.00	sqft		
4	<i>Providing and erecting in positions Cash Counters/Cash work station of approx. size 1370 x 900 x 750 mm inclusive of 1100 mm high, 350 mm wide customer writing top finished with mirror polished 18 mm thick granite slab, jet black in shade including moulding piece, fixed with chemical adhesive. The cash counters shall be made of 19 mm thick BWR grade block board finished with 1.0 mm thick laminate sheet including inner faces. Free edges shall have teak wood mouldings of half-round profile as per drawings and instructions. Inner face of modesty panel and free side are to be clad with 16 gauge M.S. sheet, painted with two coats of synthetic enamel paint of approved shade and brand over a coat of approved steel primer. Each cash work station shall comprise of the following :</i>				
	<i>Drawer unit made with 12 mm thick ply on 3 sides &amp; on bottom the front will be in 19 mm thick black board. Cash drawers having slots for keeping cash of different denominations with approved telescopic channels for drawer - slides, automatic locks (keys in duplicate) and other necessary hardware and accessories including satin finish S.S. handles of approved quality ; Readymade keyboard drawer of engineering plastic (KD 575 PMT/NNOFITT SYSTEMS OR Equivalent approved make) and all necessary accessories, suitably suspended below tabletop. The front of the cash counters shall have 12 mm thick float glass in two pieces at slides with polished teak wood glazing beads as per instructions and drawings. The item shall include 10 mm thick glass on front of the counter .Up to 48 " ht.</i>	10.00	Rft		
5	<i>Providing and fixing in position notice board as per drawing and confirming to the following specifications. Basic Frame work : Well seasoned hard wood sections, treated with two coats of wood preservatives, minimum 50 x 25 mm, at suitable horizontal/vertical spacing not exceeding 600 mm c/c. Skin membrane : 4 mm thick BWR grade plywood over which 12 mm thick approved quality soft board clad with fabric of approved shade and quality. Edge moulding : All free edges shall have polished 2nd class teak wood moulds of approved shape (finished 50 x 25 mm sections) with spirit polish in mat finish.</i>	30.00	sqft		

6	<p>Providing and erecting in position Manager's Tables as per drawing and conforming to the following specifications : Basic structure of 19 mm thick BWR grade block board for sides, top and modesty panel, finished with 1.00 mm thick laminate sheet of approved shade and make including inner faces. Drawer-cum-cabinet unit of approximate overall size of 400 X 500 X 600 mm (w X d X h) OF 19 mm thick BWR grade block board and 12/6 mm thick BWR grade plywood. The drawer unit shall comprise of 3 sliding drawers. The drawers unit shall be finished with 1.00 mm thick laminate sheet of approved shade. Inner faces of cabinet shutters/drawers shall be painted with 2 coats of white synthetic enamel paint over a coat of wooden primer. Readymade keyboard drawer if engineering plastic (KD 575 PMT/INNOFIT SYSTEMS OR Equivalent approved make) and all necessary accessories, suitably suspended below table top; Quoted rates shall also include cost of</p>				
	<p>polished teak wood moulding (finished 40 X 20 mm section) to edges of table top ; polished teak wood lipping (6 mm thick) to free edges of block board/plywood surfaces ; Approved drawer-slides, hinges and locks with keys in duplicate ; other necessary hardware and accessories including satin finish S.S. handles, knobs and wire-managers etc of approved quality. a) Approx size of 1800 X 900 X 750 mm b) Approx size of 1500 X 900 X 750 mm</p>	1.00	nos		
8	<p>Providing and erecting in position Officer's Tables as per drawing and conforming to the following specifications : Basic structure of 19 mm thick BWR grade block board for sides, top and modesty panel, finished with 1.00 mm thick laminate sheet of approved shade and make including inner faces. Drawer-cum-cabinet unit of approximate overall size of 400 X 500 X 600 mm (w X d X h) OF 19 mm thick BWR grade block board and 12/6 mm thick BWR grade plywood. The drawer unit shall comprise of 3 sliding drawers. The drawers unit shall be finished with 1.00 mm thick laminate sheet of approved shade. Inner faces of cabinet shutters/drawers shall be painted with 2 coats of white synthetic enamel paint over a coat of wooden primer. Readymade keyboard drawer if engineering plastic (KD 575 PMT/INNOFIT SYSTEMS OR Equivalent approved make) and all necessary accessories, suitably suspended below table top; Quoted rates shall also include cost of</p>				
	<p>polished teak wood moulding (finished 40 X 20 mm section) to edges of table top ; polished teak wood lipping (6 mm thick) to free edges of block board/plywood surfaces ; Approved drawer-slides, hinges and locks with keys in duplicate ; other necessary hardware and accessories including satin finish S.S. handles, knobs and wire-managers etc of approved quality. a) Approx size of 1800 X 900 X 750 mm b) Approx size of 1500 X 900 X 750 mm</p>	2.00	nos		
9	<p>Providing and erecting in position side/back cabinet units with sliding shutters of approx. size of 400 mm deep X 700 mm high made of 19 mm thick BWR grade block boards including intermediate shelves as per drawing/instructions. Exposed block board surfaces shall have finished with 1.00 mm laminate sheet of approved shade and make inner faces of sliding shutters shall be polished in approved colour. Free edges of block board shall have polished steam beech/teak wood half round moulds (out of 20 X 20 mm sections). Quoted rates shall include cost of necessary hardware, viz. handles, locks with keys in duplicate, etc. (Actual face area will be measured for payment purpose).</p>	90.00	sqft		

10	<p>Supplying and erecting rectangular low height counters/clerical workstations (1200 X 750 X 750 mm) supported on side pedestals made of BWR grade block boards , low height partitions systems and/or intermediate block boards supports as per drawing and instructions. The top shall be 18 mm thick mirror polished jet black granite slab of approved quality fixed with chemical adhesive over 19 mm thick BWR grade board of approved quality including machine cut and polished on exposed surfaces and edges, all complete as per directed. Inner face of modesty panel . The underside of the block board and inner faces of modesty panel and free sides are to be painted with two coats of synthetic enamel paint of approved shade and brand over a coat of approved wooden primer. Each workstation shall comprise of a drawer unit ,keyboard drawer similar to that of a Manager's/Officer's tables as per specified in item no.1 above, including finishing,hardware and accessories. The item shall include 10 mm th. itched glass on front of the counter .Up to 18 " ht.</p>	15.00	RFT		
11	<p>Supplying and erecting free-standing suggestion box of overall size 450 mm long X 300 mm deep X 900 mm high made of 19 mm thick phenol formaldehyde block board,all as in drawing, complete with hardware fittings and fixtures of approved make and quality. Top and all exposed surfaces of block board are to be finished with 1 mm thick laminate sheet of approved shade and quality. Liner faces of block board surfaces are to be finished with minimum two coats of synthetic anamel paint of approved shade qality over a coat of approved primer.</p>	1.00	Nos.		
12	<p>Supplying and erecting cheque drop box(overall size 450 mm long X 300 mm deep X 750 mm )made of 19 mm thick phenol formaldehyde bonded ply board and the curved portion at top made out of 90 X 90 mm C.P. teak wood section. A slit opening of 10 mm X 150 mm All the exposed timber surface including all free edges are to be finished with 1 mm thick laminate sheet of combination shade. Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer. Rate to include cost of necessary hardware fittings e.g. brass hinges,lock knob etc of approved designed quality.</p>	1.00	Nos.		
13	<p>Supplying and erecting wall mounted Customers writing ledge of approx size 900 X 300 mm made of 12 mm thick machine polished smoke glass supported on decorating wrought iron wall brackets of suitable size and quality with vacuum bush including making slots made of glass as above for keeping forms/slips.</p>	1.00	Nos.		
14	<p><b>METER BOX</b> :: P/F in position of meter box . The side shall be made out of MS frame &amp; grill etc. complete internal surfaces of the box shall be painted with enamel paint. Only front elevation area will be measured.</p>	28.00	SQFT		

15	<b>Al. MAIN DOOR</b> - Providing and fixing Glass door comprising approximate 85-100mm size top and bottom aluminum powder coated rails as per shade approved by bank . The thickness of the aluminium section should not be less than 2.5 mm. The door should be provided with everite make heavy duty floor spring ,SS hinges, cilp sections 12 mm thk clear glass of modi float /saintgobin make , customised color door hendle the rate should be inclusive of making arrangments for fixing entrance access lock with situable aluminium box section adjoining the main door .(with all complete fitting & fixture etc.)	35.00	Sq.ft.		
16	<b>Al. PARTITION</b> - Providing and fixing full Glass aluminium partition powder coated as per shade approved by the bank . The thickness of the aluminium section should not be less than 1.6 mm and size shall be approx. 63.5 x 38.5 mm. The partiton should be provided with 6 mm thk clear float glass of modi /saintgobin make, the rate should be inclusive of neoprin beading ,making arrangments for fixing entrance access lock with situable aluminium box section adjoining the main door .	62.00	Sq.ft.		
18	Providing and fixing in position <b>Arm strong false ceiling</b> in design ' in 600x600 mm x12 mm th. ( Classic Lite Tagular ) tile with tagular edge frame work as specified by Arm strong company with suspenders wherever required .Making necessary frame work for AC ducting , if any , and necessary cot out for difusers and light fittings , taping & finishing to proper line and level , including making grooves and trap doors for AC units in MR grade 12 mm th. . complete in all respect .( Note - : Only the plan area will be measured for the purpose of contractor 's payment , no extra payment shall be given for design)	1005.00	Sq.ft.		
19	Providing and febricating shutter boxes 'covered with '6mm th. commercial ply & 1mm th laminate of approved shade.A another color of approved shade 6" wide band shall 'also be provided, horizontally or vertically or both as per instruction of the architect rest pannelling shall have 2/8" groove after every 2'-0" interval .	100.00	Sq.ft.		
20	<b>NIGHT LATCH LOCKS</b> :: P/F of night latch lock make godrej. It shall have 7 brass lever with mechnism that deadlocks, suitable for rieght handed of left handed, inside or outside opening door, safet, catch to prevent entry even by the keys out side, a special safety provisions to prevent accidental lock out, scratch resistant powder coated. All complete to the satisfaction of the Bank.	2.00	Nos.		
21	<b>MORTICE LOCK</b> :: P/F of 7" mortice lock with handle set of godrej make. It shall have 6brass lever, suitable for reight or left handed door shutter, inside or outside opening. The keyless latch shall be opened from either side of the door by turning th handle, itshall work as a latch from inside at the turn of a button and as a lock operable with a key from outside. The item should be complete in all respect including fixing in place to the satisfaction of the Bank.( Fusion rossette-2-c of godrege make code 7729) including lock body ( code 8448) and 2 c -70mm cyleinder ( code 8452)	2.00	Nos.		



22	HYDRAULIC DOOR CLOSERS :: P/F of hydraulic door closer godrej make, it shall incorporate, body manufactured from aluminium extruded alloy machined to extreme accuracy, rack and pinion made of machined alloy steel duly heat - treated, adjustable closing speed, suitable for right hand and left hand opening door, suitable for door / frame mounting, suitable for door weight up to 60 kgs, suitable for 180/100 degree door opening. All complete in all respect to the satisfaction of the Bank, item is inclusive of fixing of the door closures.( item code 1938 of godrege of equivalent	2.00	Nos.		
23	S/F of door Stopper	6.00	Nos.		
			<b>Total RS</b>		
<i>Add .....% GST Extra</i>					
			<b>Say RS</b>		
<b>Contractor Signature</b>					

**ALLAHABAD BANK : ZONAL OFFICE  
CROSS ROAD MALL SINKANDARA BODLA ROAD, AGRA.  
TENDER FOR THE ELECTRICAL WORK (BRANCH+ATM)**

**BADPUR, FARRUKHABAD.**

S.N O	Description of items	Quantity	Unit	Rate	Amount in RS
1	Supply and fixing of light & Fan points with 2No.s of 1.00 Sq. mm PVC insulated copper Conductor wire in Pvc Conduit and PVC accessories like bend, J- Box, MS box, suitable sheet, 5Amp. One way switch modular type (shoket 5 pin 6 Amp for light plug point) fixing the pipe and with chassing of wall and making it good with cement mortar 1:5. Some points may require ceiling rose or button holder complete in all respect including connection, testing and commissioning etc. complete. One switch control by one point.	64.00	No.s		
2	Supply and fixing of power points with MS Box, sheet and 16 Amp. Switch modular type and shocket making with chassing of wall and making it good with cement mortar 1:5 complete in all respect including connection and testing, PVC conduit etc. complete.	18.00	No.s		
3	Supply and Fixing 1 No. of Telephone shocket with MS Box and suitable sheet, PVC conduits and PVC accessories including chassing of walls and making it good with cement mortar 1:5 including connection and testing etc. complete.	3.00	No.s		
4	Supply and Fixing UPS, output terminal Box with 1 No. of 16 Amp 6 pin socket and 2 No.s of 6 Amp. 5 pin shocket, 1 No. of 6 Amp. modular Switch with suitable sheet and MS box (PVC Box) making with chassing of walls and making it good with cement mortar including connetction, testing etc. complete. The item shall also include the supply and fixing of conduit ,wires , etc. wherever chassing not possible.	15.00	No.s		

5	Supply and fixing of 2 No.s of 2.50 Sq. mm and 1 No. of 0.75 Sq mm PVC insulated copper conductor wires in and including PVC conduit fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio including Connecting ,testing etc. compete for Light & fan circuits, power points, UPS output etc.	380.00	Rmt.		
6	S/F/C/T of 60A phase selector DB with MS enclosure having 3 No. of 60A 4 way Rottary switch and prewired factory fabricated.	1.00	Nos.		
7	Supply and fixing of 2 No.s 6.0 Sq. mm and 1 No. of 2.50 Sq mm PVC insulated copper conductor wires in and including PVC conduit fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio including Connecting ,testing etc. compete for AC circuits, Light & fan DB circuits,UPS incomer wiring, main connection wiring etc.complete.	120.00	Rmt.		
8	Supply and fixing of 2 No.s 4.00 Sq. mm plus 1x1.50 Sq mm with PVC insulated copper conductor wires in and including PVC conduit fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio including Connecting ,testing etc. compete for AC circuits main connection wiring etc.complete.	140.00	Rmt.		
9	Supply and Fixing of 8 way SPN DB MS painted factory fabricated with 1 No. of 32 Amp DP MCB and 6 No.s of 6 - 32 Amp SP MCB complete with connection , testing,complete for UPS out put circuits , Power & Light & fan Circuits .	1.00	No.s		
9A	Same as above but 4 way TPN db with 12 No. of MCCB and 1 nos. 63 A TPN MCB.	2.00	No.s		
10	Supply & fixing of 32 Amp metal clad socket & plug top double pole AC box having with 1 nos. of 25 Amp SP MCB.	7.00	No.s		
11	Same as but 4 way SPN DB with 4x6 SP MCB	3.00	No.s		
12	Supply & F/T/C of 63 A TPN MCB with Encloser.	3.00	No.s		
13	Supply and Fixing of 1 No. of 2 pair telephone wire in and including PVC conduit in/ on walls including chassing wherever required and making it good with cement mortor in 1:5 ratio complete connection, testing etc.	120.00	Rmt.		
14	Supply and Fixing 2 way SPN DB with 1 No.s of 40 Amp. DP MCB for UPS incomer complete with connection and testing etc.	4.00	No		
15	Supply and Fixing Ino.s of 12 watt pin type LED Lamp with suitable holder .	8.00	No		

16	Supply , fixing, testing and commissioning of 1 x 36 watt surface mounted LED light 18 watt complete eith wall mouting clamps.	10.00	No.s		
17	S/F/T/C of LED panel 600mm x 600mm 36 watt with complete fitting.	13.00	No.s		
18	S/F/T/C of LED 15 watt down lighter.	4.00	No.s		
19	Supply , fixing, testing and commissioning of 1200 mm ceiling fan with down Rod of crompton Grieves / Orient make with step type regulator etc. complete.(fan rod size as per site requirement)	9.00	No.s		
19a	Same as above but 900 mm ceiling fan.	2.00	No.s		
20	Supply , fixing, testing and commissioning of Earthing electrode with suitable digging and back fill compound ( use 50 L Ishan make electrode & back fill compound ) 1 for Neutral earth of UPS 1 for computer Earthing and 1 for Branch Body Earth.	4.00	No.s		
21	Supply & fixing of 400 mm Wall fans (Crompton / Bajaj / Orient )	2.00	No		
22	Supply and fixing of 25X3 MM GI strip from earth pit to Main board.	30.00	RM		
23	Supply , fixing, testing and commissioning of one no.of Cat 6E data cable in and including PVC pipe.Including RJ 45 connector.	300.00	RM		
24	Supply , fixing, testing and commissioning of one no.info outlet box with srface place & PVC box.	11.00	No.s		
25	Supply , fixing, testing and commissioning 1.5M mtr. Patch cord wire Of cat-6-E	15.00	No.s		
26	Supply and Fixing of 9 U RACK for modem & switch fixing .	1.00	No		
27	Supply and Fixing of 1 no.s of 100 Amp- cut out with netural link for DG incoming fitted on wooden board .	1.00	No		
28	12" dia Exhaust fans (Crompton / Bajaj / Orient )	2.00	No		

29	Supply & fixing of 3 nO.s of 100 Amp fuse cut out with Netural link & wooden board	1.00	set		
30	Supply & fixing of 6mm PVC insulated copper Ind cable with proper lug crimping.	200.00	rmt		
31	Dismantling of refixing of ceiling fan, ups output sheet, switch, CFL etc.	1.00	Job		
32	Supply, Fixing, Testing & commissioning 63 Amp DP MCB With Enclosure.	4.00	Nos		
33	Supply, Fixing, Testing & commissioning of 2nos. Of 10 A SPMCB with ms encloser.	2.00	Nos		
	<b>PANEL</b>				
34	Supplying, fabrication, fixing, interconnection, testing & commissioning of cubical type main panel made from 2mm thick CRCA sheet, M.S. channel for fixing on wall complete with MCCBs, MCBs meters C.T. etc complete in all respect, insulated bus bar with heat shrinkable PVC sleeve in suitable bus-bar chamber, wiring, name plate, earth-bus etc & comprising of compartments with hinged doors & rubber gasket, bus-bar chamber with bolted door and rubber gasket etc. The panel being of dust & vermin proof construction and to be painted with primer and smoke gray paint (minimum two coats) to look attractive. The panel should be comprising with the followings: (Degree of Protection IP-54). Provision of hooter in case of an accident of fire in panel complete as required.				
	125A MCCB 4 Pole with shunt trip coil	1 Nos.			
	160A 4Pole onlode changeover	1 Nos.			
	300A TPN Aluminium Busbar	1 Nos.			
	63A YPN MCB	5 Nos.	1.00	Nos.	
				<b>Total RS.</b>	
				<b>SAY RS</b>	
	Note :				
	1. All distribution Boards must be Earthed				
	2. All socket must be earthed .				
	<b>Contractor Signature</b>				

## LIST OF APPROVED MAKES

### APPROVED LIST OF MATERIALS FOR FURNISHING WORK OF ALLAHABAD BANK BADPUR, FARRUKHABAD.

( To be attached with every tender and signed by the contractor )

All Materials Shall confirm to relevant standards and ISI marked

1	Prelaminated board (exterior type)	Novopan / Bhutan
2	Commercial ply	Truwood / Archid / Century ( BWR grade main product)
3	Laminates	Newmika / Century lam / Marino Truwood / Archid / Century ( BWR grade main product)
4	Commercial Boards	
5	Local Wood	Chir / holac
6	Adhesives	Fevicol SH
7	Locks	Godrej /Cam
8	Hardwares	Eral Bihari / Hettich
9	Door Closers	Godrej / Ozone
10	Nails Screws	G.K.W./ Nettle Fold
11	Anti temite Chemical	Durs Ban TC
12	Glass	Modi / Saint Gobin
13	Teak Wood	CP Teak
14	Paints	ICI Dulux / Asian paints / Berger
15	Leatherite	Bhor
16	Venetian Blinds	Vista /Mac
17	Polish	Melamine
18	Beading	C.P.Teak Wood / Cedar
19	Wood prservatives	Bison by British paints / Termiseal by PCI
20	False Ceiling	Armstrong / Indian Gypsum Board
21	Night latch	Godrej
22	Aluminium door frames	Jindal
23	aluminium Cladding	Euro Bond / Alto bond / Aluk bond
24	keyboard drawer	EBCO / Godrej
25	telescopic CPU stand	EBCO
26	Cable organiser ( Wire Manager )	EBCO
27	Vitrified tiles	Euro / RAK/ Simpolo/ Itaca
28	Perforated chairs	Godrej / Durian

Note- Ply wood & board mentioned in the drawings as well as in bills of quantities should be BWR grade only.

Signature & seal of the contractor

#### NOTE:

- Any brands indicated under the items specifications in the schedule of quantities will prevail over the above indicated makes.
- Apart from the above makes, any further equivalent make as approved by the Bank, can also be used with prior permission from the Bank.

## LIST OF APPROVED MAKES

### APPROVED LIST OF MATERIALS FOR ELECTRICAL WORK OF ALLAHABAD BANK BADPUR, FARRUKHABAD.

( To be attached with every tender and signed by the contractor )  
All Materials Shall confirm to relevant standards and ISI marked

1	MCB,MCCB,ELCB,RCCB, Isolator ,MCB,DB'S	Legrand / L & T / MDS
2	Power Factor Panel (automatic correction )	siemens / Neptune
3	Contactors O/L Relay	L&T/ Legrand
4	Indicating Lamps & Push Butttton	L&T / Rishabh / AE
5	AmP/ Volt Meters	L&T / AE
6	Changeover/ selector ( Rotary ) Switches	L&T/ HPL
7	CTs	L&T/ Rishab / AE
8	Terminal Blocks	ELEMEX /Connectwell
9	Wires - copper /aluminium	Finolex / Polycab
10	MS Conduit	BEC/ AKG
11	P.V.C Conduits	BEC/ AKG
12	Switches & Sockets	Philips (Modular ) / Legrand / North west
13	Lighting & Fixtures & Luminaries	Philips / Bajaj
14	Ceiling Fans	Crompton Greaves
15	Exhaust Fans	Crompton Greaves
16	Cables	Finolex / Grandlay
17	Cables Trays	Pilco / Stotco
18	GI Pipes	BST / Jindal
19	Telephopne Wires	Finolex / Polycab
20	TAG Block	ITI / Krone
21	A / C Box	L&T/ Legrand
22	PA system accessories	Ahuja / Philips
23	Lead Acid Batteries	Exide / Panasonic
24	Battery chagers	Logicstat/ V-Guard / Kiranotics
25	Voltage Stabilizer	Logicstat / Usha Rectifier /Kiranotics
26	Cable Management Runner	LK INDIA / Pilco
27	HRC Fuses	HPL / L& T
28	Speaker	Philips / Sony
29	MCB BOX /Distribution board	L & T / Legrand / MDS
30	Data cable	D-Link
31	I.O. Box	D-Link
32	R.J.45 Connector	D-Link
33	Communication Rack	D-Link / Com. Rack / Data Rack

Signature & seal of the contractor

#### **NOTE:**

- Any brands indicated under the items specifications in the schedule of quantities will prevail over the above indicated makes.
- Apart from the above makes, any further equivalent make as approved by the Bank, can also be used with prior permission from the Bank.