

ALLAHABAD BANK
(Head Office, 2, N.S.Road, Kolkata)

NOTICE INVITING TENDER

**Work: Tender Interior Furnishing & Extension electrical work for proposed Retail & MSME Processing
centre at
Zonal Office Agra**

Sealed item rate tenders from empanelled contractors are invited for furnishing work and electrical work in RMPC at First floor cross road mall Sikandra bodla road agra. Full details and tender documents are available on Bank's website: www.allahabadbank.in or may be collected from Bank's Zonal Office Agra at Plot no. G.P. 5 & 6, First Floor Cross Road Mall, Pt. Deen Dayal Upadhyay Puram Sikandra Agra – 282007.

Duly filled in tenders should be submitted as per following schedule at Allahabad Bank, Zonal Office agra at Plot no. G.P. 5 & 6, First Floor Cross Road Mall, Pt. Deen Dayal Upadhyay Puram Sikandra Agra – 282007.

1.	Issue of tender document	From 12.04.2019 to 26.04.2019
2.	Time of completions	10 days
3.	Submission of tender	Tenders should be placed in sealed cover with the name of work written on the envelopes addressed to The Deputy General Manger, Zonal Office Agra on or before 26.04.2019 up to 17.00 hrs at Plot no. G.P. 5 & 6, First Floor Cross Road Mall, Pt. Deen Dayal Upadhyay Puram Sikandra Agra – 282007.
4.	Opening of tender	On 29.04.2019 at 11.00 hrs
5.	Liquidated damages for delays	Should the work not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to 1% of the accepted tendered per week subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un commenced or unfinished after expiry of the Completion date.
6.	Payment terms	No advance will be paid. Final Payment will be made on satisfactory Completion of the job on the basis of actual measurements. Income tax will be Deducted as per the rules.
7.	Defect Liability Period	Retention money 10% will be deducted from the bill and to be released after 12 Months from the date of virtual completion provided no defects are observed during this period.
8.	Validity of Tender	90 Calendar days
9.	Transportation and lifting	The rates quoted should include cost of Materials transportation, carting, wastages and lifting for all leads, night work, Labor etc.

The Bank will not be bound to accept the lowest tender and reserve the right to accept or reject any or all the tender without assigning any reason whatsoever. Late/delayed tender shall not be accepted after Last date and time of submission of tender.


Dy. General Manager

ALLAHABAD BANK : ZONAL OFFICE					
CROSS ROAD MALL SINKANDARA BODLA ROAD, AGRA.					
QUOTATION FOR EXTENSION INTERIOR FURNISHING WORK					
ZONAL OFFICE AGRA					
S.N.	ITEM DESCRIPTION	QTY	UNIT	Rate	AMONT Rs.
1	Wall painting (one coat) with plastic emulsion paint of approved brand and manufacture on decorative wall surface to give an even shade including thoroughly brushing the surface clean all of dirt, grease loose pieces and prepare smooth.	340.00	sqft		
2	Supplying and erecting running counter in server room 600 mm deep and 750 mm high including CPU or computer , modesty panel , etc made with 19 mm thick phenol formaldehyde bonded block board on top and supporting sides with necessary well seasoned hard wood frame work,finished on top and sides with 1 mm thick laminate of approved shade and quality ,supported on 19 mm thick laminate of approved shade and quality ,supported on 19 mm thick BWR grade block board including providing and fixing 450 mm long powder coated steel key board tray of approved shade. Work shall include keyboard drawer and CPU holders similar to that of other workstations including inishing,hardware and accessories at each of the workstation. The keyboard is to be suspended from hte tabletop,all complete as in drawing.				
	All exposed edges of block board are to br provided with half round steam beech/teakwood mouldings, duly polished. Inner faces of wooden/block board surfaces are to be finished with minimum two coats of synthetic enanel paint of approved shade and quality over a coat of approved primer.Rate to include charges for brass hardware fittings as well as fixtures like sliding gear for drawers of "Earl Behari" of similar approved make.	32.00	RFT		
3	Providing and fixing of vertical blinds made out of 100mm wide (Scotch - Guarded) fabric louvers (as per shade approved by the Architect) including Head rail, control unit carries, Tilter, Traverse cord, Tilt rod bottom Machanism, Installation Bracket etc. all Complete.	66.00	sqft		
4	Dismantling of old furnishing.	1.00	Job		
				Total Rs	
	Note :			Add @.....% G.S.T	
				G.Total Rs.	
	Contractor sign.				

ALLAHABAD BANK : ZONAL OFFICE					
CROSS ROAD MALL SINKANDARA BODLA ROAD, AGRA.					
QUOTATION FOR EXTENSION ELECTRICAL WORK					
ZONAL OFFICE AGRA					
S.NO	Description of items	Quantity	Unit	Rate	Amount in RS
1	Supply and fixing of light & Fan points with 2No.s of 1.00 Sq. mm PVC insulated copper Conductor wire in Pvc Conduit and PVC accessories like bend, J- Box, MS box, suitable sheet, 5Amp. One way switch modular type (shoket 5 pin 6 Amp for light plug point) fixing the pipe and with chassing of wall and making it good with cement mortar 1:5. Some points may require ceiling rose or button holder complete in all respect including connection, testing and commissioning etc. complete. One switch control by one point.	3.00	No.s		
2	Supply and fixing of power points with MS Box, sheet and 16 Amp. Switch modular type and shocket making with chassing of wall and making it good with cement mortar 1:5 complete in all respect including connection and testing, PVC conduit etc. complete.	2.00	No.s		
3	Supply and Fixing 1 No. of Telephone shocket with MS Box and suitable sheet, PVC conduits and PVC accessories including chassing of walls and making it good with cement mortar 1:5 including connection and testing etc. complete.	2.00	No.s		
4	Supply and Fixing UPS, output terminal Box with 1 No. of 16 Amp 6 pin socket and 2 No.s of 6 Amp. 5 pin shocket, 1 No. of 6 Amp. modular Switch with suitable sheet and MS box (PVC Box) making with chassing of walls and making it good with cement mortar including connetction, testing etc. complete. The item shall also include the supply and fixing of conduit ,wires , etc. wherever chassing not possible.	7.00	No.s		
5	Supply and fixing of 2 No.s of 2.50 Sq. mm and 1 No. of 0.75 Sq mm PVC insulated copper conductor wires in and including PVC conduit fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio including Connecting ,testing etc. compete for Light & fan circuits, power points, UPS output etc.	200.00	Rmt.		
6	Supply and fixing of 2 No.s 4.00 Sq. mm plus 1x1.50 Sq mm with PVC insulated copper conductor wires in and including PVC conduit fixing on walls or chassing the walls and making it good with cement mortar of 1:5 ratio including Connecting ,testing etc. compete for AC circuits main connection wiring etc complete	124.00	Rmt.		
7	Supply and Fixing of 8 way SPN DB MS painted factory fabricated with 1 No. of 32 Amp DP MCB and 6 No.s of 6 - 32 Amp SP MCB complete with connection , testing, complete for UPS out put circuits , Power & Light & fan Circuits .	1.00	No.s		

8	Supply & fixing of 32 Amp metal clad socket & plug top double pole AC box having with 1 nos. of 25 Amp SP MCB.	1.00	No.s		
9	Supply and Fixing of 1 No. of 2 pair telephone wire in and including PVC conduit in/ on walls including chassing wherever required and making it good with cement mortor in 1:5 ratio complete connection, testing etc.	80.00	Rmt.		
10	S/F/T/C of LED panel 600mm x 600mm 36 watt with complete fitting.	2.00	No.s		
11	Supply , fixing, testing and commissioning of 1200 mm ceiling fan with down Rod of crompton Grieves / Orient make with step type regulator etc. complete.(fan rod size as per site requirement)	1.00	No.s		
12	Supply , fixing, testing and commissioning of one no.of Cat 6E data cable in and including PVC pipe.Including RJ 45 connector.	200.00	RM		
13	Supply , fixing, testing and commissioning of one no.info outlet box with srface place & PVC box.	7.00	No.s		
14	Supply , fixing, testing and commissioning 1.5M mtr. Patch cord wire Of cat-6-E	7.00	No.s		
15	12" dia Exhaust fans (Crompton / Bajaj / Orient)	2.00	No		
16	S/F/T/C of 8 port Ethernet Switch.	1.00	No		
17	S/F/T/C of 5 port Ethernet Switch.	1.00	No		
				Total Rs	
	Note :			Add @.....% G.S.T	
				G.Total Rs.	
	Contractor sign.				