

**Allahabad Bank**  
**Disaster Recovery Site, 3<sup>rd</sup> Floor ZO Building, Hazratganj, Lucknow**

**Notice Inviting Tender (NIT) For LAN Cabling (Cable Laying, Tie & Tagging) at DRS-Lucknow**

There is urgent requirement of LAN Cabling in our Data Centre between server rack and network rack having distance approx. 30 mtr. The requirement of LAN cabling and related accessories is being appended below. The interested local bidders may participate in the tendering process and accordingly they may submit us the appended format(schedule of quantities required ) **latest by the 25.04.2018 up to 3.00 PM . The tenders will be opened on the same day at 4.00 PM.**

The Bidder must be empanelled vendor/reputed vendor having experience of LAN cabling in Data Centre Setup or similar kind of setup. The relevant order copy of last three year should be attached along with the tender format. The preference will be given to experienced Bidder who has worked on similar nature of job in PSB/Govt. Organizations. It is suggested that interested bidders may visit the location for better understanding of current setup as well as of proposed setup including items and services intended.



**(Chief Manager-IT)**



**Schedule of Quantities For LAN Cabling (Cable Laying, Tie & Tagging)**  
**At Allahabad Bank at DRS-Lucknow**

S. No.	Description of Item(s)	Make	Quantity (Approx.)	Rate/Unit	Tax GST	Total Amount (in Rs.)
1	Cat-6 UTP Cable 23 AWG (48 cable length approx. 42 meter each cable 48x42 = 2016 meter will be used)	D-Link	2000 mtr.			
2	Patch Panel 24 Port loaded cat 6	D-Link	04			
3	Patch Cord 3 meter(Standard Ready made)	D-Link	48			
4	Patch Cord 5 meter (Standard Ready made)	D-Link	32			
5	Patch Cord 10 meter(Standard Ready made)	D-Link	10			
	*Total Amount in words					

(\* Final Total cost of work will be calculated as per actual consumption)

**Terms & Conditions :-**

1. All the items used will be of make original D-LINK and will be under replacement warranty of 1 year.
2. The cost is inclusive of cable laying/tagging/crimping and punching etc. ie. Complete in all respect. Laying of cables will be through already installed cable tray(s) & existing cables patch panels will be removed by the bidder without any extra charges. The work will be completed in co-ordination of all the stake holder as per Bank's decision.
3. The 90% payment will be released after completion of satisfactory completion of work along with submission of Lan Tester/ Penta Scanner testing reports of end to end points. Remaining 10% will be released after three months from the successful commissioning /acceptance .
4. Must be completed within 2 days after issuance of Purchase Order.
5. TDS will be deducted as per norms.



**Signature of Authorized Signatory**

**(with stamp)**